

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15051-00426-00-00

API NUMBER N/A
LEASE NAME Eunice Lieb
WELL NUMBER #1
330 Ft. from (S) Section Line
3960 Ft. from (E) Section Line
SEC. 8 TWP. 11 RGE. 16 (E) or (W)
COUNTY Ellis

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR V. Francis Weigel
ADDRESS P.O. Box 244 Gorham, Kansas 67640
PHONE# (913) 637-5383 OPERATORS LICENSE NO. 6772

Date Well Completed _____
Plugging Commenced 4-17-85
Plugging Completed 4-17-85

Character of Well _____
(oil) Gas, D&A, SWD, Input, Water Supply Well)
Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? Hays office.
Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3037 Bottom 3183 T.D. 3375

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|---------|----|--------|--------|------------|
| KC | | Surface | | 8 5/8" | 1017 | None |
| | | | | 4 1/2" | 3375 | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged 8 5/8" with 50 sacks cement down backside, Max. pressure 500#, Shut in 150#.
Mixed 4 sacks hulls - 25 sacks cement - 12 sacks gel - Release plug - 100 sacks
cement down 4 1/2" casing. Max. pressure 500#, Shut in 200#. Cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc.
Address P.O. Box 31 Russell, Kansas 67665


RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Russell

MAY 28 1985
15-28-85

V. Francis Weigel
(Employee of Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) V. Francis Weigel
(Address) P.O. Box 244 Gorham, Ks. 67640



SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 85

Mary Ann Weigel
Notary Public

My Commission Expires: March 16, 1987