


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

~~XXXXXX~~ Ellis County, Sec. 8 Twp. 11 Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 NW/4 SW/4  
Lease Owner Frontier Oil Company  
Lease Name Frontier Oil Company-E. Lieb Well No. 4  
Office Address \_\_\_\_\_  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced December 13 19 59  
Plugging completed December 15 19 59  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3416 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3416 feet to surface feet for each plug set.  
Pipe had been set at 3412 ft. Hole filled with sand to 3400 ft; four sacks of cement placed in hole with dump bailer; Pipe shot off at 2705; and pulled to 480 feet; pump trucks circulated with 20 sacks of mud, and 20 sacks of cement pumped down to 480 feet; pipe then pulled to 150 feet and 20 sacks cement pumped down; All of pipe pulled from hole, and holed bailed down to 30 feet and capped with 10 sacks of cement

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1960  
01-07-60  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Barnes and Sons Pipe Pulling co  
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 South West Bank Bldg Wichita, Kan. (Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 1960  
My Commission expires 11-17-62  
Mapine Head Notary Public.



