


15-051-00324000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 9 Twp. 11 Rge. 16 (EW (W))
Location as "NE/CNW&SW&" or footage from lines SE SW SW
Lease Owner Lee Phillips Oil Company
Lease Name Craig Well No. 1
Office Address 1407 Union Nat'l Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 9, 1959 19 59
Application for plugging filed November 9, 1959 19 59
Application for plugging approved November 9, 1959 (verbally) 19 59
Plugging commenced November 9, 1959 19 59
Plugging completed November 9, 1959 19 59
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface		0	222'	8 5/8"	222'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 390' with plug and 20 sacks of cement at this point. Mud to 180' with plug and 20 sacks of cement mud to 40' with plug and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms-Burt Drilling Company
Address P. O. Box 184, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Allan Harms (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
P. O. Box 184, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23 day of November, 1959
Mary E. Van Pelt
Notary Public.



15-051-00324-0000

DRILLERS LOG

Company: Lee Phillips Oil Company
Farm: Craig #1
Commenced: October 31, 1959

SE SW SW Section 9-11-16W
Ellis County, Kansas
Completed: November 9, 1959

Elevation: 1811 KB

0 - 80	shale
80 - 120	shale & sand
120 - 390	shale
390 - 485	sand
485 - 700	shale
700 - 975	red bed and shale
975 - 1010	anhydrite
1010 - 1136	red bed & shale
1136 - 1270	shale
1270 - 1600	shale shells
1600 - 2215	lime & shale
2215 - 2600	shale & lime
2600 - 2865	lime & shale
2865 - 3335	lime
3335 - 3395	conglomerate
3395 - 3425	lime & shale
3425 - 3450	Arbuckle
3450	Total depth

NOV 24 1959
CONSERVATION DIVISION
Wichita, Kansas

Set 222' feet of 8 5/8" surface casing. Cemented with 175 sacks of cement with 2% calcium chloride.

Tops: Anhydrite	975
Heebner	2974
Toronto	2997
Lansing KC	3021
Conglomerate	3318
Arbuckle	3418

Drill Stem Test #1 2990-3030 Open 1 hour. Shut in 30 min. Recovered 30' mud BHP-1005#

Ran electric log.

Dry, plugged and abandoned.

A F F I D A V I T

STATE OF KANSAS)
)SS
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms

Subscribed and sworn to before me this 23 day of November, 1959.

Mary E. Van Selt

My commission expires January 20, 1962

