


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
311 No. Broadway
Wichita, Kansas

Ellis County, Sec. 8 Twp. 11 Rge. 16 (E) W (W)
SW/4

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner **Frontier Oil Company**
Lease Name **Frontier Oil Co.-E. Lieb** Well No. **3**
Office Address **580 Fourth National Bank Bldg. Wichita, Ks**
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced **March 28** 19 **59**
Plugging completed **March 30** 19 **59**
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes.**

Name of Conservation Agent who supervised plugging of this well **Eldon Petty**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **3412** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from **3412** feet to **surface** feet for each plug set.

Hole filled with sand from 3412 to 3385) Pipe preforated at 3395) Dumped four sacks of cement in hole with dump bailer; Pipe then pulled to 500 feet and pump trucks circulated mud, and pumped down 25 sacks of cement to 500 ft; remainder of pipe then pulled to to 160 ft, and 20 sacks of cement pumped down to 160 ft; Remainder of pipe pulled and bailed hole down to forty feet; ten foot rock bridge installed between 40 and 30 feet and hole capped with 10 sacks of cement.

1045 feet of surface pipe left in hole, having been circulated with cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor **Barnes and Sons Pipe Pulling Co.**
Address **Russell, Kansas.**

STATE OF Kansas COUNTY OF Sedgewick, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Natl. Bank Bldg
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 19 59
My commission expires 11-17-62
Notary Seal Notary Public.



PLUGGING
FILE SEC. 8 T. 11 R. 16w
BOOK PAGE 28 LINE 30

DRILLING LOG

#3 EUNICE LIEB

CASING RECORD: 8 5/8" @ 1045' with 450 sacks cement
5 1/2" @ 3412 1/2' with 125 sacks cement
TOTAL DEPTH: 3413' (-1568)

COMPANY: Frontier Oil Company
CONTRACTOR: Red Tiger Drilling Co.
COMMENCED: July 8, 1957
COMPLETED: July 19, 1957

DESCRIPTION: NW 8E SW 8-118-16W Ellis County, Kansas
ELEVATION: 1842 DF 1845 RB

FORMATION	FROM	TO	REMARKS
Surface Soil and Clay	0	40	
Sand and Shale	40	170	
Shale and Shells	170	425	
Sand	425	580	
Shale and Shells	580	590	
Iron or Hard Sand	590	600	
Sand	600	670	
Shale, Shells Red Bed	670	1035	
Anhydrite	1035	1070	
Shale and Shells	1070	1650	
Shale and Lime	1650	2840	
Lime	2840	3250	
Lime and Shale	3250	3276	
Lime	3276	3322	
Lime and Conglomerate	3322	3400	
Simpson Sand and Shale	3400	3404	
Lime	3404	3413	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Roy McClure
Roy McClure

Subscribed and sworn to before me this 13th day of August, 1957

Mattie Head
Notary Public

My Commission Expires:

11-17-58