

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER <sup>15-</sup> 051-24663-0000

LEASE NAME C.P.A.I.C.

WELL NUMBER C #1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4950 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 16 TWP. 11S RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 6-19-90

Plugging Commenced 2-12-91

Plugging Completed 2-12-91

LEASE OPERATOR Eric Waddell Co.

ADDRESS Box 349 Natoma, Ks. 67651

PHONE# (913) 885-4497 OPERATORS LICENSE NO. 6725

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-10-90 (date)

by Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Non-Commercial Depth to Top 3069 Bottom 3271 T.D. 3462

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC 3069-72	Watery oil	0	220	2 5/8	208'	0
Macomb 3271-77	Dry	0	3462	4 1/2	3461	Top 10' feet
LKC 3228-82						
3203-07-3177-81	Dry					
3094-97						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged back with sand from T.D. to 3050. Put 10 sks cement on top of sand. Pumped 375 sk, 4 5/8 8 7/8 gel w/ 300# Halls until cement circulated to surface. (First 250 sk. pumped down casing, last 125 sk w/ 50 Halls pumped down annulus.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor NA Supervised by KCC official from Hays License No. \_\_\_\_\_

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ERIC F. WADDELL

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

ERIC F. WADDELL (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Eric F. Waddell

(Address) Box 349 Natoma, Ks 67651



SUBSCRIBED AND SWORN TO before me this 10 day of May, 19 91

MAY 13 1991

CONSERVATION DIVISION

My Commission Expires: 3-28-92

Notary Public