

15-051-01076-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA old well  
LEASE NAME CRAIG #3  
WELL NUMBER #3  
SPOT LOCATION SE NE SW  
SEC. 16 TWP. 11 SRGE. 16 (50) (W)  
COUNTY Ellis  
Date Well Completed 6-29-63  
Plugging Commenced 2-19-88  
Plugging Completed 2-19-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.  
ADDRESS 151 N. Main Suite #700 Wichita, Ks. 67202  
PHONE (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well SWD EOR  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes  
Which KCC/KDHE Joint Office did you notify? Dist. #4  
Is ACO-1 filed? NA old well If not, is well log attached? yes

Producing formation NA Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3349

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	8 5/8"	set @	953'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran 40 jts. tubing, mix and pump 35 sks 60/40 pozmix, Squeezed casing, to 900#, layed down tubing, Tied onto 8 5/8 csg. mix and pumped 265 sks 60/40 pozmix.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Warrior Drilling Co. Rig # License No. 5883  
Address 151 N. Main #700 Wichita, Ks. 67202

RECEIVED  
STATE CORPORATION COMMISSION  
03-03-88  
3 1988

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr. (employee of operator) or CONSERVATION DIVISION  
~~XXXXXX~~ above-described well, being first duly sworn on oath, says: That Wichita, Kansas  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) F.W. Shelton, Jr.  
(Address) 905 Century Plaza, Wichita, Ks. 67202



SUBSCRIBED AND SWORN TO before me this 1st day of March, 1988

Martha E. Gustin  
Notary Public  
Martha E. Gustin Notary Public

My Commission expires: Mo 4-15-89