

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 16 Twp. 11 Rge. 16 ~~XX~~ (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SE

Lease Owner E. H. Riggs

Lease Name Finch Well No. 1

Office Address 408 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 26 1958

Application for plugging filed May 26 1958

Application for plugging approved May 26 1958


Plugging commenced May 26 1958

Plugging completed May 26 1958

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3405' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 450'. Set Plug #1 at 450' with 20 sacks cement. Filled hole from Plug #1 to 240' with extra heavy rotary mud. Set Plug #2 at 240' cemented with 20 sacks cement. Filled Hole with extra heavy rotary mud from Plug #2 to 40'. Set Plug #3 at 40' cemented with 10 sacks cement and 1/2 sack Hulls.

RDW
06-03-58 JUN 1958
CONSERVATION
WICHITA

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814 Union Center, Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol

814 Union Center, Wichita, Kansas (Address)

Subscribed and sworn to before me this 2nd day of June, 19 58



Darlene May Notary Public.

PLUGGING
FILE SEC 16 T. 11 R. 16W
BOOK PAGE 105 LINE 20

15-051-19197-0000

ROTARY DRILLING LOG

OPERATOR: E. H. Riggs
FINCH NO. 1
SW SW SE Sec. 16-11S-16W,
Ellis County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 5/13/58
COMP: 5/26/58

Remarks: Set 8-5/8" surface casing
at 280' cemented with 175 sacks Pozmix,
2% C.C.

Formations:

Surface Clay & Rock	25'
Sand & Gravel	110'
Blue Shale	125'
Shale & Shells	340'
Sand & Shale	540'
Sand & Red Bed	950'
Anhydrite	980'
Shale & Shell	1270'
Shale & Lime	1505'
Lime & Shale	2010'
Lime	2060'
Lime & Shale	2445'
Shale & Lime	2550'
Lime & Shale	2735'
Lime	3236'
Marmaton	3279'
Lime	3317'
Simpson	3345'
Lime & Shale	3356'
Arbuckle	3405'
Rotary Total Depth (D&A)	3405'

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 16 T. 11 R. 16W
BOOK PAGE 105 LINE 20