

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: C. C. Nelson Drilling Company
 FARM: Lundy #1
 LOCATION: Sec. 16-11S--16W SE SE SE
 Ellis County, Kansas
 COMMENCED: October 2, 1946
 COMPLETED: October 17, 1946

0	to	10	Surface
10	to	480	Shale and shells
480	to	502	Sand
502	to	510	Iron and lime
510	to	555	Shale
555	to	610	Sand
610	to	640	Shale
640	to	895	Red bed and shale
895	to	974	Red bed and shale
974	to	990	Anhydrite
990	to	1014	Anhydrite
1014	to	1090	Red bed and shale
1090	to	1500	Red bed and shale
1500	to	1650	Shale
1650	to	1710	Shale and shells
1710	to	1745	Lime
1745	to	1775	Shale and shells
1775	to	1900	Sandy lime and sand
1900	to	2360	Lime
2360	to	2380	Shale
2380	to	2500	Shale and shells
2500	to	2640	Lime and shale
2640	to	2740	Shale
2740	to	3035	Lime
3035	to	3078	Lime and shale
3078	to	3350	Lime
3350	to	3375	Conglomerate & chert.
3375	to	3405	Conglomerate
3405	to	3430	Lime--Top arbuckle 3403
3430	to	3455	Lime
		3455	T.D. **Top of derrick floor

LOGGING
 FILE 16-11-16W
 BOOK PAGE 77-24

Set 990 ft. of 8 5/8 inch surface pipe. Cemented with 300 sacks cement.

Top anhydrite 972, top Lansing 3028, top conglomerate 3324, top arbuckle 3403.
 DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Lundy #1, Sec. 16-11S-16W, Ellis County, Kansas, as reflected by files of the Nelson Drilling Company.

Subscribed and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 21 day of October 1946.

My commission expires May 25, 1949

C. C. Nelson
Esther Russell

