


15-051-01018-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County. Sec. 16 Twp. 11 Rge. (E) 16(W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Craig Well No. 1
Office Address 522 Union Center, Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-29-57 19
Application for plugging filed 12-29-57 19
Application for plugging approved 12-29-57 19
Plugging commenced 12-29-57 19
Plugging completed 12-29-57 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3369 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	950	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud to 500, pushed plug to 500, 20 sack cement thru 16 joints drill pipe. Filled hole to 240, plug to 240, 20 sack cement, mud to 40, 1/2 sack hulls, plug, cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of January, 19 58

My Commission expires June 4, 1959

Helen Horine
Notary Public.



PLUGGING
FILE SEC 16 T 11 R 164
BOOK PAGE 73 LINE 33

15-05-01018-0000

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Craig
SW SW NE, Sec. 16-11-16W,
Ellis County, Kansas

D & A
Elevation 1797 KB

Commenced: 12-17-57

Completed: 12-29-57

Set 950' of 3 5/8" surface csg. w/450 sax

Contractor: Rupp-Ferguson Oil Co.

Figures Indicate Bottom of Formation

- 40 surface soil & clay
- 360 clay & blue shale
- 410 sand
- 540 rock, shale & sand streaks
- 635 sand
- 800 red rock & shale
- 937 red bed
- 979 Anhydrite
- 1225 red bed & shale
- 1350 shale & shells
- 1638 salt & shale
- 1965 lime
- 1983 lime & shale
- 2145 lime, shale & sand streaks
- 2200 lime & shale
- 2245 shale
- 2500 shale & shells
- 2735 shale, shells & lime
- 2880 lime
- 2945 lime & shale
- 3209 lime
- 3274 lime & shale
- 3365 Cong. & Imp.
- 3369 Arb. T.D.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1958

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Craig well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before us this 2nd day of January, 1958.

Helen Horine
Notary Public

My Commission Expires June 4, 1959.

PLUGGING
FILED SEP 16 T 11 R 164
BOOK PAGE 73 LINE 33