


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-051-02050-000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 17 Twp. 11 Rge. 16 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NW/4
Lease Owner Frontier Oil Company
Lease Name Frontier Oil Co-Chesney Well No. 4
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Dec 10 19 59
Plugging completed Dec. 12 19 59
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3393 feet to surface feet for each plug set.

Pipe had been perforated between 3386 and 3370 ft; Hole filled with sand from 3393 to 3360 ft; three sacks of cement placed on bottom of hole with dump bailer; pipe then shot off at 2761 ft, and pulled to 500 feet; Pump trucks pumped down 16 sacks of mud, followed by 20 sacks of cement; pipe then pulled to 150 ft and 20 sacks of cement pumped down hole; balance of pipe pulled from hole and 10 additional sacks of mud pumped into well.

RECEIVED
STATE CORPORATION COMMISSION
RWD
JAN 7 1960
01-07-60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Sedgewick, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth Nat Bank Bldg Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 1960
Notary Seal
Notary Public.



DRILLERS LOG

#4 CHESNEY

CASING RECORD: 1022' of 8 5/8" with 450 sacks cement,
 3389' of 4 1/2" with 150 sacks cement

TOTAL DEPTH: 3390'

COMPANY: Frontier Oil Company
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: October 30, 1956
 COMPLETED: November 11, 1956

DESCRIPTION: NE SW NW
 17-11S-16W
 Ellis County,
 Kansas

ELEVATION: 1817' DF
 1819' RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	45	
Shale and Shells	45	90	
Shale, Shells & Sand	90	400	
Shale and Shells	400	440	
Sand	440	470	
Shale	470	490	
Sand	490	600	
Shale and Shells	600	775	
Red Bed	775	1012	
Anhydrite	1012	1045	
Red Bed, Shale & Shells	1045	1495	
Shale and Shells	1495	1585	
Lime and Shale	1585	2185	
Shale	2185	2345	
Shale and Lime	2345	2945	
Lime	2945	3265	
Lime and Shale	3265	3370	
Lime	3370	3378	
Shale and Lime	3378	3381	
Lime	3381	3390	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Roy McClure

Subscribed and sworn to before me this _____ day of November, 1956

Notary Public

My Commission Expires: _____