

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-20012-0000

API NUMBER 2-8-67

LEASE NAME Chesney "A"

WELL NUMBER #1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 17 TWP. 11S RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 2-8-67

Plugging Commenced 6-17-91

Plugging Completed 6-17-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 100 N. Main, Suite 500 Wichita, Kansas 67202

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-17-91 (date)

by Dennis Hemel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached?

Producing Formation Simpson Sand Depth to Top 3309 Bottom 3313 T.D. 3313

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Casing		0	965'	2 7/8 5/8	965'	none
Production Casing		0	3309	5' 5 1/2	3309.5'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Rigged up and perforated Anhydrite at 975' with 3 shots. Rigged up Plains Well Service. Ran tubing to 3180'. Rigged up BJ Services and pumped 140 sx cement (60/40 Pozmix with 8% gels). Pulled tubing to 900'. Circulated 100 sx cement to surface. Pulled tubing. Mixed 165 sx down 5 1/2" casing. Maximum pressure 300#, shut in 100#. Rigged off. Cut off surface pipe

(If additional description is necessary, use BACK of this form.) below ground and filled pit.

Name of Plugging Contractor BJ Services License No. _____

Address P.O. Box 69 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.


Richard A. Hiebsch

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch

(Address) Richard A. Hiebsch, Vice President
 100 N. Main, Suite 500 Wichita, KS

AND SWORN TO before me this 2nd day of October, 19 91



Julie K. Stout
 Julie K. Stout, Notary Public

My Commission Expires: July 23, 1993