

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32334
Name: Chesapeake Operating, Inc.
Address 1: P.O. Box 18496
Address 2: _____
City: Oklahoma City State: OK Zip: 73154 + 0496
Contact Person: David Wiist, Production Engineer
Phone: (405) 935-3906

API No. 15 - 081-20695-5890
If pre 1967, supply original completion date: _____
Spot Description: _____
C - NE Sec. 22 Twp. 27 S. R. 34 East West
4,620 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: Oliver Well #: 1A-22

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1,920' Cemented with: 795 Sacks
Production Casing Size: 5 1/2" Set at: 5,280' Cemented with: 250 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Mississippi (5030'-4'); St. Genevieve (5096'-100'); St. Louis (5129'-32' & 5156'-60')

Elevation: 3006 (G.L. / K.B.) T.D.: 5,290' PBDT: 5,238' Anhydrite Depth: 1825'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

See attached procedure

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging required by KCC regulation.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Bud Neff, Production Superintendent

Address: 4532 W. Jones Avenue City: Garden City State: KS Zip: 67846 + _____

Phone: (620) 277-0803

Plugging Contractor License #: 999916 Name: Allied Cementing Co., Inc.

Address 1: P.O. Box 31 Address 2: _____

City: Russell State: KS Zip: 67665 + _____

Phone: (785) 483-2627

Proposed Date of Plugging (if known): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5-27-10 Authorized Operator / Agent: _____

David Wiist

(Signature)

Digitally signed by David Wiist
DN: dc=net, dc=chkenergy,
ou=Users and Groups, cn=David
Wiist, email=david.wiist@chk.com
Date: 2010.05.26.16:23:59 -05'00'

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Oliver 1A-22
P&A
5-14-10

Procedure

1. Notify KCC District 1 at least 5 days before plugging operations
KCC District 1: (620)225-8888
2. MIRU WOR, POOH with pump & rods. ND WH, NU BOP, TOO H with 2 7/8" tubing.
3. PU 5 1/2" CIBP, TIH with plug and set at $\pm 4980'$. Dump 2 sx cement w/2% CaCl_2 on top of CIBP (Plug 1). TOO H w/tubing while circulating plugging mud.
4. TIH with tubing, pump the following plugs in casing displacing with plugging mud:

Plug 2: Shoe plug (1900'-2050')	40 sx. w/ 2% CaCl_2
Plug 3: Fresh water plug (800'-950')	40 sx w/ 2% CaCl_2
Plug 4: Surface plug (44'-4')	10 sx. w/ 2% CaCl_2
5. Cut off casing 4ft. below ground level, weld on steel ID plate. RDMO WOR.



Regulatory Department

May 27, 2010

VIA UNITED PARCEL SERVICE

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

Re: Oliver 1A-22
22-27S-34W
Haskell Co., KS
API #15-081-20695

Dear Sir or Madam:

Enclosed is a CP-1 form for the referenced well.

If additional information is required, please contact me at the telephone number or e-mail address below or David Wiist at (405) 935-3906. Any written correspondence regarding this well should be directed to my attention at the address below.

Sincerely,

Chesapeake Operating, Inc.

A handwritten signature in black ink that reads "Sarah Rodriguez".

Sarah Rodriguez
Regulatory Analyst

Enclosures

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman, Joseph F. Harkins, Commissioner, Ward Loyd, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

CHESAPEAKE OPERATING, INC.
6200 N WESTERN AVE
PO BOX 18496
OKLAHOMA CITY, OK 73118-1046

May 28, 2010

Re: OLIVER A #1-22
API 15-081-20695-00-00
22-27S-34W, 4620 FSL 660 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after November 24, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888