

15-129-10105 00-01

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Amoco Production Company
Complete Address Box 432, Liberal, Kansas 67901
Lease Name Cowan Gas Unit "B" Well No. 1
Location C W/2 W/2 SE NE Sec. 34 Twp. 31 Rge. 40 (E) (W)
County Morton Total Depth 6050'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A X
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling Co.
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 5:00PM Day 7 Month 5 Year 1971

The above well was plugged as follows:

8 5/8" to 714' circulated w/ cement. 5 1/2" to 5845' cemented.
Top perforations 3817' Plug bottom w/ Bridge Plug & 7 sacks cement.
Top of cement 3630' Mud 3630' to 1400'
Spott 20 sacks cement 1400' to 1350' Mud 1350' to 765'
Spotted 35 sacks cement 765' to 665' Mud 665' to 40'
Plug, Halls & 10 sacks cement 40' to 0'. Company Pump
Pulled 2295' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging Supervisor

INVOICED

DATE 5/13/71
INV. NO. 3686-41