

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-109-30052-00-00

File No. _____ County: Logan

Location: CNW SW Sec. 23 Twp 12 Rge. _____ (E) _____ (W) 34

Name of Field: _____ Total Depth: 4880

I have this date completed supervision of plugging of:

Lease Name: Vaneaton Well No. 1

Operator's Full Name: Toto Gas Co

Complete Address: 5101 Penn St Oklahoma City, Okla.

Plugging Contractor: Natural Gas Drg Co

Address: Scott City, Kansas License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9:30AM Day 4 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 248' circulated with cement -

Circulated hole with heavy mud, set cementing plug at 1030', displaced 40 sax cement through drill pipe at 1030', heavy mud to 590', displaced 25 sax cement through drill pipe at 590', heavy mud to 390', displaced 30 sax cement through drill pipe at 390', heavy mud to 240', set plug and 10 sax cement at 240', heavy mud to 30', set plug and 10 sax cement to bottom cellar.

Cementing by Halliburton Co.

Signed: Edmund Perry
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED
DATE 4/26/62
INV. NO. 4860-w