

15-051-19235-0000

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 70-36

LOCATION NE NW SW

SEC. 10 TWP. 13 RGE. 17

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Dorzweiler

Operator Anschutz Drg Co, Inc Address Wichita, Kans

Field _____ County Ellis

Total Depth 3528 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 238' circulated with cement - 5 1/2" at 3528 with
100 sax behind. Lane Wells plugs to 3441', top perf at 3342'.

Filled with chat to 3530', set 4 sax cement with dump bailer.

Pulled 2634' 5 1/2", filled hole with mud to 200', set rock bridge
and 15 sax cement, heavy mud to 35', rock bridge and 10 sax
cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1951

CONSERVATION DIVISION
Wichita, Kansas

Robert J. ...
District Conservation Agent

Date 4-18-51

PLUGGING
FILE SEC 10 TWP 13 RGE 17
BOOK PAGE 70 LINE 36