

15-051-04046-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 57-15
LOCATION SW SE SW
SEC. 10 TWP. 13 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Giebler

Operator Oil Trading Associates Inc Address 6/o K & E Drg Co
Wichita, Kans

Field _____ County Ellis

Total Depth 3537 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 166' circulated with cement - 5 1/2" at 3534' with 75
sax cement behind - P.B. to 3534' perforated at 3518'.

Filled with sand to 3500', set 4 sax cement with dump bailer,
pulled 3100' 5 1/2" - pumped hole full commercial mud (35 sax),
pumped cementing plug to 160', followed by 50 sax cement.

Cement 160' to 0' - Mudding and cementing by Globe Cementing Co.

[Signature]

District Conservation Agent

Date 5-8-56

RECEIVED
STATE CORPORATION COMMISSION
5.10.56
MAY 10 1956

PLUGGING

FILE SEC 10 T 13 R 17
BOOK PAGE 57 LINE 15

CONSERVATION DIVISION
Wichita, Kansas