

15-051-01085-0000

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-76  
NOV 16 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Kewanee Oil Company

Complete Address P/ O, Box 2093, Wichita, Kansas 67201

Lease Name Catherine Unit Well No. Tr. 3-7

Location C SE NE SE Sec. 10 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3510'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by HOWCO.

Address        License No.       

Operation Completed: Hour 12 M Day 15 Month 11 Year 1976

The above well was plugged as follows:

Total Depth 3510' 8 5/8 csg set 237' cwc 180 sx.

5 1/2 csg set 3503' cw 100 sx cem.

2 7/8" tbg fish at 720'. No pipe recovered.

Ran tbg to 720' - Halliburton Cementing Co. mixed & pumped 5 sx gel & water W/100 lbs

hulls - circulated 100 sx Comm Cem 4% gel to surface.

Down annulus (8 5/8 X 5 1/2) with 50 sx Comm Cem. 4% gel. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Messing  
Well Plugging Supervisor

INVOICED

DATE 11-16-76

INV. NO. 4163-4