

15-051-05499-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 10 TWP. 13 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Karlin

Operator Darby & Bothwell Address 612 Orpheum Bldg Wichita,

Field Catherine County Ellis

Total Depth ~~3532~~ 3546 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1199' circulated with cement - 5 1/2" at 3532 with
100 sax behind.

Filled with chat to 3525', set 4 sax cement with dump bailer,
pulled 3000' 5 1/2", filled hole with mud to 250', set rock bridge
and 15 sax cement, filled with heavy mud to 35', set rock
bridge and 10 sax cement to bottom cellar.

RECEIVED
CONSERVATION
6-4-51

Edwin P. ...
District Conservation Agent

PLUGGING
FILE SEC 10 T 13 R 17 DIVISION
BOOK PAGE 83 LINE 21

Date 5-31-51