

15-051-04670-0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Kewanee Oil Company

Complete Address P.O. Box 2093, Wichita, Kansas 67201

Lease Name Catherine Unit 'O' Well No. Tr. 3-8W1

Location C SE NW SE Sec. 10 Twp. 13 Rge. (E) (W) 17

County Ellis Total Depth 3535'

Abandoned Oil Well      Gas Well      Input Well XX SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1 P Day 26 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3535' 8 5/8 csg set at 247' cwc 160 sk.

5 1/2 csg set 3425' cw 150 sk cem.

5 1/2 csg PBTB 3380' with top perf. (3313)

Filled 5 1/2 csg W/sd (3380-3300) dumped 5 sk cem W/dump bailer. (3300-3265)

Cutoff & recovered 2668' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released

plug & 120 sk 50-50 poz 6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Bio J. Messing  
Well Plugging Supervisor

INVOICED  
DATE 3/5/75  
INV. NO. 921-W