

API NUMBER 15-051-24865-0000

LEASE NAME Dorzweiler G

WELL NUMBER 9

1650 Ft. from S-Section Line

990 Ft. from ^W Section Line

SEC. 10 TWP. 13 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 12-3-93

Plugging Commenced 12-3-93

Plugging Completed 12-3-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Cattlemans Oil Operations

ADDRESS 2260 Catherine Rd. Hays, Kansas

PHONE#(913) 625-5394 OPERATORS LICENSE NO. 7064

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-2-93 (date)

by Schumacher (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation D&A Depth to Top _____ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		surface	@250	8 5/8	250	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
 Pumped 25 sks down drillpipe @1180', 100 sks @620', 40 sks @300', 10sk. @40'

& wiper plug, 15 sks. rat hole, 10sk. mouse hole

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied License No. _____

Address P O Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cattlemans Oil

STATE OF Kansas COUNTY OF Ellis, ss.

Leo R. Dorzweiler (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Leo R. Dorzweiler

(Address) 2260 Catherine Rd. Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 24th day of December, 1993

Viola Dorzweiler
 Notary Public

My Commission Expires: 4-20-95

RECEIVED
 STATE CORPORATION COMMISSION
 12-28-93
 10:46
 28 1993
 CONSERVATION DIVISION
 Wichita, Kansas

15-051-24865-0000

DRILLERS WELL LOG

DATE COMMENCED: November 29, 1993
DATE COMPLETED: December 3, 1993

Cattlemans Oil Company
DORZWEILER B-#9
SE-NW-SW
Sec. 10-13S-17W
Ellis County, Kansas

ELEVATION: 1991' G.L.
1996' K.B.

0 - 253' Sand, Shale
253 - 315' Rock, Shale
315 - 1035' Sand, Clay
1035 - 1171' Red Bed, Shale
1174 - 1218' Anhydrite
1218 - 1545' Red Bed, Clay, Shale
1545 - 1985' Shale
1985 - 2566' Lime, Shale
2566 - 2815' Shale
2815 - 3185' Lime, Shale
3185 - 3325' Shale
3325 - 3466' Lime
3466 - 3535' Shale
3535' R.T.D.

FORMATION DATA

Anhydrite 1174'
Base Anhydrite 1218'
Topeka 2967'
Heebner 3213'
Toronto 3235'
L.K.C. 3260'
Base K.C. 3493'
Conglomerate 3512'
Arbuckle None
R.T.D. 3535'

Surface Pipe: Set 28# used
8 5/8" Casing @ 250' with
150 sacks 60/40 Poz., 2% gel,
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF RUSSELL) ss

Roy Vonfeldt of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.

Roy Vonfeldt
Roy Vonfeldt

Subscribed and sworn to before me this 15 day of December, 1993.

My Comm. Expires:

8-5-94

Debbie Maier
Debbie Maier, Notary Public

