

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Ellis County, Sec. 10 Twp. 13 Rge. 17 (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C N $\frac{1}{2}$  SE SW $\frac{1}{4}$

Lease Owner M. B. Armer

Lease Name Geibler Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed April 7 19 52

Application for plugging filed April 7 19 52

Application for plugging approved April 7 19 52


Plugging commenced April 7 19 52

Plugging completed April 7 19 52

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3544 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	195	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 3544 ft. to 185 ft., set cementing plug and 1/2 sack hulls and 15 sacks cement run through drill pipe; filled hole with mud to 35 ft., set cementing plug and 1/2 sack hulls and filled to bottom of collar with 10 sacks cement.

4-23-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woody Speer

Address 710 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 52

Hazel Twiston Notary Public.

My commission expires Sept. 17, 1955



**LOG**

Company: Armer Drilling Company, Inc.  
 Contractor: Woody Speer  
 Drilling Commenced: 3/22/52  
 Drilling Completed: 4/7/52  
 Elevation: 2007 A.B.  
 2006 B.F.  
 2004 Cr.

Farm: Gable #1  
 Location: C 1/2 SE SW 1/4 Sec. 10-13-17W  
 Ellis County, Kansas  
 Casing Record: 8-5/8" casing at 195'  
 with 100 sacks cement.

(hole drilled to 204' - Rosenbergs-Bemis Equipment Co., of Great Bend, Kansas.)

(Figures below indicate bottoms)

Shale & shells	675
Sand	835
Redbed & shells	1030
Shale & shells	1075
Shale & iron	1110
Shale & shells	1180
Anhydrite	1285
Shale	1285
Shale & shells	1595
Redbed & sand	1775
Shale & shells	1985
Shale & lime	2510
Shale & shells	2620
Shale	2780
Shale & lime	2880
Shale	3000
lime & shale	3205
lime	3544
R. T. D.	3544 D. & A.

FORMATION TOPS (R. B. Meas.)

Hebner	3221
Tarento	3240
Lansing - Kansas City	3260
Arbuckle	3520

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

WOODY SPEER

BY

*Woody Speer*

STATE OF KANSAS

COUNTY OF SEDWICK

ss:

Subscribed and sworn to before me, a notary public, in and for said County and State this 6th day of April, 1952.

*Harold Walton*  
 Notary Public

My Commission expires Sept. 17, 1955.

**PLUGGING**  
 FILE SEC 10 T 13 R 17W  
 BOOK PAGE 7 LINE 45