


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 10 Twp. 13S Rge. 17WXXX (E) (W)

Location as "NE/CNW&SW" or footage from lines C SW SE SW

Lease Owner K & E Drilling, Inc. - Oil Trading Associates, Inc.

Lease Name 1006 Central Bldg., - Giebler Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed April 9, 1956

Application for plugging filed April 30, 1956 19

Application for plugging approved April 30, 1956 19

Plugging commenced May 2, 1956

Plugging completed May 5, 1956

Reason for abandonment of well or producing formation

Commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3637 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	166'	none
				5 1/2"	1 3534'	3110'
				Hole was plugged back to 3534'. Pipe perforated 3518' to 3524' et		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3534' to 3500' and ran 4 sacks of cement. Pumped 3 sacks of mud and 50 sacks of cement to surface pipe to complete plugging.

RECEIVED
STATE CORPORATION COMMISSION
5-10-56
MAY 10 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Dale Silcott

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott

1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of May, 1956

Francis Mueller Notary Public.

My commission expires June 25, 1956

PLUGGING
FILE SEC 10 T 13 R 17W
BOOK PAGE 57 LINE 15

15-051-04046-0000

OIL TRADING ASSOCIATES, INC. - K & E DRILLING, INC.
Giebler #1

SW SE SW Sec. 10-13S-17W
Ellis County, Kansas

Comm: March 24, 1956
Comp: April 3, 1956
Total Depth: 3537

<u>Casing</u>	<u>Cement</u>
8 5/8" Set @ 166' w/ 140 sacks cement	
5 1/2" Set @ 3534' w/ 75 sacks cement	

<u>FORMATION</u>	<u>DEPTH</u>
Surface soil and clay	0 - 30
Shale	30 - 70
Shale & shells	70 - 166
Shale & shells	166 - 3200
Sand and shale	320 - 700
Sand	700 - 835
Red Bed and Shale	1070 - 1193
Anhydrite	1193 - 1233
Shale & shells	1233 - 1490
Shale - shells & salt	1490 - 1830
Shale & lime	1830 - 2845
Lime	2845 - 2945
Lime	2945 - 3250
Lime & shale	3250 - 3267
Lime (K.C.)	3267 - 3516
Arbuckle	3516 - 3537

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Dele Scott

Subscribed and sworn to before me this 5th day of April, 1956.

Frances Marler
Frances Marler

My commission expires: June 25, 1956

PLUGGING

FILE SEC. 10-13S-17W
BOOK PAGE 57 LINE 15