


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Cowley County. Sec. 31 Twp. 32 Rge. 6 (E) (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines NW NE SW
 Lease Owner McKnab - Lindsay
 Lease Name Werner Well No. B-1
 Office Address Box 808, Winfield, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
 Date well completed 5-31-60 19
 Application for plugging filed 5-31-60 19
 Application for plugging approved 5-31-60 19
 Plugging commenced 5-31-60 19
 Plugging completed 5-31-60 19
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud 3140 - 180
 Cement 180 - 135
 Mud 135 - 35
 Cement 35 - 0

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1960
CONSERVATION DIVISION
Wichita, Kansas

Rotary Plugged

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McKnab & Lindsay
 Address Box 808, Winfield, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.
V. W. McKnab (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V W McKnab
Box 808, Winfield, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 19 60

My commission expires Aug. 21, 1961

[Signature]
 Notary Public.



15-035-19420-0000

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1960

CONSERVATION DIVISION
Wichita, Kansas

WELFARE B-1
NW NE SW Sec. 31-32S-6E
Cowley County,
Kansas

Contractor: McKnab - Lindsay
Operator: McKnab - Lindsay

Date Comm: 5-31-60
Date Comp: 6-8-60

0 - 135	Cement
135 - 1868	Lime & Shale
1868 - 1955	Sand
1955 - 2212	Lime & Shale
2212 - 2260	Sand
2260 - 2287	Shale & Sand
2287 - 2312	Core #1
2312 - 2335	Sand
2335 - 2416	Sand & Shale
2416 - 2435	Lime
2435 - 2505	Sandy Shale & Lime
2505 - 2613	Lime
2613 - 2874	Lime & Shale
2874 - 2990	Shale
2990 - 3032	Sand & Shale
3032 - 3086	Lime & Shale
3086 - 3140	Miss Lime
3140	T.D.

Casing & Cement records:

232' 8 5/8" seg. cemented with 75 sks. cement and 1 centralizer.

Plugging Records:

Mud	3140 - 180
Cement	180 - 135
Mud	135 - 35
Cement	35 - 0

DST #1 2935 to 2953
Tool open 1 1/2 hrs. Shut in 20 min.
120' mud, 180' salt water, IF 15#
PF 140# NEP 1040#

DST #2 3095 to 3120
Tool open 1 hr. Shut in 30 min.
10' mud IF o PF o NEP 265#.

Acknowledged:

McKnab & Lindsay

By V W McKnab --

Date: June 10, 1960

Subscribed to and sworn to before me this 10th day of June, 1960.

William L. Lujan
Notary Public

My commission expires Aug 24, 1961