


15-035-19409-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County, Sec. 31 Twp. 32 Rge. 6 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C W/2 NE NE  
Lease Owner R. B. Asher  
Lease Name Barkman Well No. 1  
Office Address Wichita, Kansas 67212  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 11/13/73 19  
Plugging completed 11/17/73 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Graham  
Producing formation Depth to top Bottom Total Depth of Well 2296 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	150	none
				5 1/2"		1520

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 1850' and ran 5' of sand and set 5 sacks cement. Shot pipe at 1797', 1695', 1585', 1515', pulled 47 joints. Bailed hole to 200', set rock bridge and ran 4 yards ready mix.

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION

NOV 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
K VOTH CASING PULLING

Name of Plugging Contractor CHASE, KANSAS  
Address

STATE OF KANSAS, COUNTY OF RICE, ss.  
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X Walter Voth  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1973

Margaret Melcher  
Notary Public.

My commission expires MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975



**JOE E. NEWMAN #1 BARKMAN  
C W/2 NE NE SECTION 31-32s-6e.  
COWLEY COUNTY, KANSAS**

Augusta Oil Co., Inc.  
Barkman # 1  
Contract - J. E. Newman  
Cowley County, Kansas

W E L L L O G

Started September 22, 1963  
Completed September 30, 1963  
R.T.D. 3130'

190-----	380	Lime - Shale brks.
380-----	1852	Lime - Shale
1852-----	1902	Sand
1902-----	2285	Lime - Shale
2285-----	2291	Layton Sand
2291-----	2310	Sandy Shale
2310-----	2387	Lime - Shale
2387-----	2435	Lime - K.C.
2435-----	2500	Lime
2500-----	2587	Lime
2587-----	2600	Shale
2600-----	2673	Shale and Lime
2673-----	2735	Oawego Lime
2735-----	2787	Lime
2787-----	2835	Shale and Lime
2835-----	2970	Shale
2970-----	2980	Hartlesville Sand
2980-----	3040	Shale - Sandy Shale
3040-----	3060	Lime - Cherty Lime
3060-----	3077	Miss. Lime
3077-----	3130)	Lime
3130-----		R. T. D.