

6 030848

JAN 2 1 1987

API NUMBER 15-109-20323-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C/SW/SE, SEC. 12, T. 12 S, R. 34 W

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name MOORE "H" Well # 1

Operator: PETROLEUM INC.

County LOGAN 155.16

Name & Address 300 W DOUGLAS

Well Total Depth 4774 feet

#800 RH GARVEY BLDG.

Conductor Pipe: Size \_\_\_\_\_ feet

WICHITA, KANSAS 67202

Surface Casing: Size 8 5/8 feet 257'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BJT TITAN License Number \_\_\_\_\_

Address OAKLEY, KANSAS

Company to plug at: Hour: AM Day: 21 Month: 1 Year: 19 86

Plugging proposal received from EVERETT JONES

(company name) PET. INC. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 257' w/ 16 SX 5 1/2 SET @ 4774 w/ 12.5 SX PORT COLLAR

WOULDN'T OPEN SO CSG. WAS PERFORATED @ 2633' (ANHY) 10' BELOW COLLAR

AND BWC w/ 700 SX. CMT. TOPPER. 4651'-59' ORDERED 250 SX.

THIRTY MIX. 65/95 POZ 10% GEI 2% DICEID 5 SX. HULLS B-J. TITAN CMT. CO.

LARUE WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:40 AM Day: 21 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT MIX. & Pump Down 5 1/2" CSG 10 bbl CMT. SLURRY

(20 SX) FOLLOWED BY 5 SX. HULLS MIXED IN WITH (240 SX.) 120 bbl

CMT SLURRY LOADED HOLE AND SQUEEZED TO 800\* MAX. PSI.

CLOSED IN @ 800\* PSI.

MIX & Pump Down 8 5/8" - 5 1/2" ANNULUS 5 bbl CMT SLURRY (10 SX)

PRESSURED UP SHUT IN @ 400\* PSI. PLUG. COMPLETE

Remarks: STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form)

INVOICED

DATE 2-2-87

INV. NO. 16045

JAN 30 1987  
01-301987  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)