

6 030455

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: BEREN CORPORATION

Name & Address 970 4TH FINANCIAL CTR.

WICHITA, KANSAS

67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address BOX 347 CHASE, KANSAS 67524

Company to plug at: Hour: PM Day: 24 Month: 5 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING PULLING (phone) _____

were: 8 5/8 SET @ 327' w/ 250 SX. CEM. 5 1/2 SET @ 4844' w/ 750 SX. CEM. O.H.

5 1/2 SQUEEZED TO SURFACE. ORDER SAND AND 10 SX. CONC. CEM. PLUG BOTTOM, SHOOT PIPE

AND STRIP PIPE SHOTS AT 1000', 900', 800', 600', 570' TWICE NO PIPE RECOVERED.

ORDER 180 SX. 50/5000L 6 7/8 IN 3 1/2 IN 40 SX. GEL 4 1/2 IN. HULLS. SUN CEM. CO.

WELLBROOK WATER TRUCK'

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:40 AM Day: 24 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT BOTTOM PLUG. 5 SX. CONC. CEM. W/ BAILER ON BOTTOM, SAND TA (280) 4690,

5 SX. CONC. CEM. W/ BAILER ON SAND, TOP PLUG, Pump Down 5 1/2' w/ 204 CONC. CEM.

10 SX. BEL. 160 SX. CEM. MIX. MAX. PSI 500# @ 1/2 BBL/AIR. CLOSE IN @ 150#

PLUG COMPLETE

Remarks: _____

(If additional description is necessary, use BACK of this report)

I (did/did not) observe this plugging.

DATE 6-9-85

INV. NO. 8411

API NUMBER 15-109-20160-00-00

NESW, SEC. 4, T. 12 S., R. 34 W. 0

1980 feet from S section line

3300 feet from E section line

Lease Name HENRY Well # 1

County LOGAN 157.47

Well Total Depth 4845' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 327'

RECEIVED
STATE CORPORATION COMMISSION

JUN 05 1985
06-05-1985
CONSERVATION DIVISION
WICHITA, KANSAS

Signed Carl Goodnow
(TECHNICIAN)