

4-060704

7-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-109-20,588-00-00

SW SE NW SW /4 SEC. 12, 12 S, 34 W
1440 feet from S section line
720 feet from W section line

Operator license# 3966 Lease: Stanley Hays Well # 2
Operator: Wanker Oil County: Logan 153.27

Address: R.R. 2 - Box 14 Well total depth 4716 feet
WaKeeney, Kansas 67672 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 inch @ 256 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 11:30 P.M. Day: 6 Month: July Year: 1995

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: 913-635-1511

Were: Order 200 sxs. 60/40 posmix - 6% gel - 1/4# F.C. per sack.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All, Part, None X

Completed: Hour: 11:30 P.M., Day: 6, Month: July, Year: 1995

Actual plugging report:

1st. Plug at 2675' w/25 sxs. - Anhydrite 2655' - 2677'.

2nd. Plug at 1500' w/100 sxs. - Dakota 1196' - 1496'.

3rd. Plug at 310' w/ 40 sxs. - Surface pipe at 256'.

4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 21 1995
07-21-1995
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING Elevation: GL

If I did not X observe the plugging.

[Signature]
(agent)

INVOICED

DATE 7-28-95

INV. NO. 43193