

9-16

4-020053

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-109-20,568-00-00
NE NE SE /4 SEC. 14, 12 S, 34 W
2200 feet from S section line
440 feet from E section line

Operator license# 05011
Operator: Viking Resources, Inc.
Address: 105 S. Broadway, Suite 1040
Wichita, Kansas 67202

Lease: Conner Well # 1
County: Logan
Well total depth 4780 feet ^{155.35}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 208 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: J. V. Mallard, Inc. License# 04958

Address: 2080 E. Kansas - P.O Box 1009, McPherson, KS 67460

Company to plug at: Hour: Day: 16 Month: September Year: 1994

Plugging proposal received from: Carol

Company: J. V. Mallard, Inc. Phone: 316 241 4640

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

<u>1st plug @ 2670 feet with 25 sacks</u>	<u>Rat hole: 15 sacks</u>
<u>2nd plug @ 1520 feet with 100 sacks</u>	<u>Mouse hole: 10 sacks</u>
<u>3rd plug @ 260 feet with 40 sacks</u>	
<u>4th plug @ 40 feet with 10 sacks</u>	

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1994
09-20-1994
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Ken Kuhn
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 8:15PM, Day: 16, Month: September, Year: 1994

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X, NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 3172 GL

I did / did not X observe the plugging. Ken Kuhn
(agent)

INVOICED
DATE 10-10-94
41395