

4-110050

9-11-98

API Number: 15-051-02, 701-0002

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NW SE SE \_\_\_\_\_ /4 SEC. 10, 13 S, 17 W  
990 feet from S section line  
990 feet from E section line

Operator license# 7064

Lease: Dorzweiler "G" Well # 2

Operator: Cattleman's Oil Operations

County: Ellis 115.05

Address: 2260 Catherine Road  
Hays, Kansas 67601

Well total depth 3540 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Cattleman's Oil Operations License# 7064

Address: 2260 Catherine Road - Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 11 Month: September Year: 1998

Plugging proposal received from: Leo Dorzweiler

Company: Cattleman's Oil Operations Phone: 785-625-5394

Were: According to KCC Rules & Regulations.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 12:00 P.M., Day: 11, Month: September, Year: 1998

Actual plugging report: 8 5/8" set at 200' - cement amount unknown. 5 1/2" casing at 3518' with 175 sxs cement. Squeezed at 1150' w/250 sxs cement and 300# hulls. Squeezed at 2785' w/300 sxs common and 200 sxs pozmix. Squeezed at 1520' w/380 sxs common and 120 sxs pozmix. Ran tubing to 1700' - pumped 25 sxs cement with 100# hulls. Pulled to 1500' and shut down for 3 hours. Pumped 75 sxs cement with 300# hulls. Pulled to 450' - pumped 30 sxs cement with 150# hulls. Pulled rest of tubing and topped off with 30 sxs cement. Tied to 8 5/8" x 5 1/2" annulus pressured to 300# Max. Took no cement. Total 160 sxs 60/40 pozmix with 10% gel and 550# hulls.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 2000 GL

I did  / did not [ ] observe the plugging.

Rogers & Moses  
(agent)

⓪

Form CP-2/3

INVOICED

DATE SEP 30 1998

INV. NO. 51391

GIEBLER BROTHERS

#2

GIEBLER

10-13-17W  
NW SE SE

Contr. EARL WAKEFIELD

ELLIS

County

E. 2004RB Comm. Comp. 10-4-57 IP 175 BOPD

Tops	Depth	Datum
KC	3265	-1261
ARB	3515	-1511
TD	3525	-1521

Casing

8" 200

5" 3518

00 3525

CATHERINE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS