

3-2-88

15-035-00454-0001
Docket #D-18,201

To: ² 050660
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D & C 11-16-55
NW SW SE, SEC. 31, T 32 S, R 6 ~~W~~E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5394
Operator: R.R. Abderhalden
Name & Address 510 Hardage Center
Wichita, KS 67202

Lease Name Werner Well # 1 SWD
County Cowley 80.44
Well Total Depth 2475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 90

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Company Tools License Number _____
Address _____

Company to plug at: Hour: 8:00am Day: 2 Month: 3 Year: 1988

Plugging proposal received from Dick Stout

(company name) R.R.A., Inc. (phone) _____

were: 5 1/2" set @2471' w/100 sxs cement. Perf @2350'-80'. Set wireline plug @2100'
Run 2" to 2008' and spotted 20 sxs cement on plug. Shoot and pull pipe.
Bridge @350' and fill to surface with cement.

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30pm Day: 2 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Set wireline plug @2100'. Ran 2 3/8" tubing to 2008' and spotted
20 sxs cement on plug. Shot and pulled 900' of 5 1/2" casing. Bridged @350'.
3:00pm 3-2-88 Ran 2" tubing to 350', pumped 200 sxs 60/40 poz, no cement
returned. Shut down.
3-9-88 2:00pm Ran 2" tubing and tagged up on cement @120'. Circulated
cement to surface.

Remarks: United #1149 3-11-88
MAR 11 1988
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging. Wichita, Kansas

Signed Glen W. Ward
(TECHNICIAN)

DATE 3-14-88
INV. NO. 20104
3-2