

12-22

To: 6 031206  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,398-00-00  
SE SE SE, SEC. 1, T 10s, R 33W/E  
330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
6039  
Operator License #  
Operator: L.D. Drilling Inc.  
Name & Address: R. R. 1 Box 183B  
Great Bend, Ks. 67530

Lease Name Kuska Well # J 1  
County Thomas 153.08  
Well Total Depth 4710 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cement Co. License Number \_\_\_\_\_  
Address Russell, Ks.

Company to plug at: Hour: AM Day: 22 Month: Dec Year: 19 88

Plugging proposal received from Pete Fiorini  
(company name) L D Drilling Inc. (phone) \_\_\_\_\_

were: 8 5/8" set at 345' w/275 sks. 4 1/2" set at 4709' w/250 sks. D.V. tool  
set at 2630' w/500 sks cwc. Perf 4447' - 4451'. Order 350 sks 65/35 Poz 10% Gel 2% Dicol  
500# Hulls. Allied Cement Co. Cheyenne Water Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
1-18-89  
JAN 10 1989

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 22 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 4 1/2" w/225 sks cement w/500# Hulls mixed  
into max psi 200#. Close in psi 200#. Plug complete. Squeezed 8 5/8" w/125 sks cement  
200# Hulls to max psi 300 #. Close in 150#.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED  
DATE 1-19-89  
NO. 23710  
12-22

Signed Carl Goodrow  
(TECHNICIAN)