

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3941
Name: LB Oil
Address 1: 211 - 8th Street
Address 2: _____
City: Clafin State: KS Zip: 67525 + _____
Contact Person: Todd Morgenstern
Phone: (620) 564-3728
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-25420-00-00
Spot Description: _____
NW SW NE _____ Sec. 22 Twp. 18 S. R. 11 East West
1,640 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Kaiser Well #: 2
Date Well Completed: D & A
The plugging proposal was approved on: 06-11-10 (Date)
by: Pat Bedore (KCC District Agent's Name)
Plugging Commenced: 06-13-10
Plugging Completed: 06-13-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8" new 23#	324'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug well with 185 sacks of 60/40 Poz, 4% gel, 1/4# floseal per sack.
1st plug @ 3297' with 25 sacks. 2nd plug @ 570' with 25 sacks. 3rd plug @ 320' with 80 sacks.
4th plug @ 40' with 10 sacks to surface. Plug mouse hole with 15 sacks. Plug rat hole with 30 sacks.
Job complete @ 3:00 p.m. on 06-13-10 by Allied (tk #41540)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc.
Address 1: PO Box 276 Address 2: 8 North Main
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 564-3800
Name of Party Responsible for Plugging Fees: LB Oil

CONSERVATION DIVISION
WICHITA, KS

State of Kansas County, Barton, ss.
Renee Kasselmann, Office Manager for Southwind Drilling, Inc. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Renee Kasselmann 06-14-10

[Handwritten signature]

SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS

Lease: Kaiser #2

Plugging received from KCC representative:

Name: Pat Bedore Date 6-11-10 Time 9:00 A.M.

1st plug @ ~~3297~~ 3297 ft. 25 sx. Stands: 53½

2nd plug @ 570 ft. 25 sx. Stands: 9½

3rd plug @ 320 ft. 80 sx. Stands: 5½

4th plug @ 40 ft. 10 sx. Stands: 1

5th plug @ _____ ft. _____ sx. Stands: _____

Mousehole 15 sx.

Rahole 30 sx.

Total Cement used: 185 sx.

Type of cement 60/40 poz 4% gel ¼" Flo Seal per sx

Plug down @ 3:00 P.M. 6-13-10

Call KCC When Completed:

Name: Bruce Basye Date 6-14-10 Time 9:41 AM

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., LLC. 041540

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>6-13-10</u>	SEC. <u>22</u>	TWP. <u>18</u>	RANGE <u>11</u>	CALLED OUT	ON LOCATION	JOB START <u>2:30p</u>	JOB FINISH <u>3:00p</u>
LEASE <u>Kaiser</u>	WELL # <u>2</u>	LOCATION <u>Clabbe 1E 325</u>			COUNTY <u>Carters</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>W.F.</u>							

CONTRACTOR Southern Ry # 2

TYPE OF JOB PTA

HOLE SIZE 7 7/8 T.D. 3359

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2 DEPTH 3327

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED _____

COMMON _____ @ _____

POZMIX _____ @ _____

GEL _____ @ _____

CHLORIDE _____ @ _____

ASC _____ @ _____

EQUIPMENT

PUMP TRUCK: CEMENTER _____

417 HELPER Shane

BULK TRUCK _____

778 DRIVER Hiatt

BULK TRUCK _____

_____ DRIVER _____

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 14 2010
CONSERVATION DIVISION
WICHITA, KS

HANDLING _____ @ _____

MILEAGE _____ @ _____

TOTAL _____

REMARKS:

3297 25 sks

570 25 sks

320 50 sks

40 10 sks

Ret H/c 30 sks Misc H/c 15 sks

CHARGE TO: LA Oil

STREET 211 E Street

CITY Clabbe STATE KS ZIP 67521

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE _____ @ _____

MILEAGE _____ @ _____

MANIFOLD _____ @ _____

TOTAL _____

To Allied Cementing Co., LLC,
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

Dry Hole Plug @ _____

_____ @ _____

TOTAL _____

PRINTED NAME _____

SIGNATURE William Sanders

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS