

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior  
Address 1: P.O. Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Kevin Wiles  
Phone: (620) 275-2963  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: D-27,773  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 4842 Bottom: 4851 T.D. 6225  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 03-00028-0002  
Spot Description: C-NE-NE-SW  
C NE NE SW Sec. 17 Twp. 33 S. R. 18  East  West  
2,319 Feet from  North /  South Line of Section  
2,335 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Comanche  
Lease Name: Hackney Well #: #1 SWD  
Date Well Completed: 8/18/1966  
The plugging proposal was approved on: 4/22/2010 (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Plugging Commenced: 04/22/2010  
Plugging Completed: 04/27/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	13 3/8	261	None
		Surface	8 5/8	2667	None
		Production	5 1/2	5245	3500

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 22 2010  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4680', 2sx cement on CIBP, cut casing at 3500', lay down, run tubing to 1st 990', pump 20 sx gel, 50sx 60/40 poz 2% gel, 2nd 290', 50sx 60/40 poz, 3rd 60', 20sx 60/40 poz, circulate to surface 5/11 - Measure down surface, cement at 20', measure conductor, cement down 6', back fill cellar

Plugging Contractor License #: 5105 Name: Clarke Corporation  
Address 1: P.O. Box 187 Address 2: 107 W. Fowler  
City: Medicine Lodge State: Kansas Zip: 67104 + \_\_\_\_\_  
Phone: (620) 886-5665  
Name of Party Responsible for Plugging Fees: American Warrior  
State of Kansas County, Barber, ss.  
Mark Morgenstern  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern

*Handwritten initials*