

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chesapeake Operating, Inc.
Address: P.O., Box 18496, Oklahoma City, OK 73154-0496
Phone: (405) 935-3906 Operator License #: 32334
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-5-09 (Date)
by: Steve Bond (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Wreford Depth to Top: 2,309 Bottom: 2,778 T.D. 2,840
Red Eagle Depth to Top: 2,618 Bottom: 2,624 T.D. 2,840
Indian Cave Depth to Top: 2,748 Bottom: 2,778 T.D. 2,840

API Number: 15-007-20827-0002
Lease Name: Jewell A
Well Number: 1-6
Spot Location (QQQQ): _____ - W2 - W2 - SW
1,320 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 6 Twp. 30 S. R. 11 East West
County: Barber
Date Well Completed: 5/29/1980
Plugging Commenced: 2/25/10
Plugging Completed: 2/26/10 *Ka*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Wreford	Gas	0	2839'	4 1/2"	2839'	1773'
Red Eagle	Gas	0	251'	8 5/8"	251'	0'
Indian Cave	Gas					

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 09 2010
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See Attachment.

(TREATABLE WATER LEVEL: Minimum 500' OR 20' INTO THE Permian.)

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: HA 99996
Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Chesapeake Operating, Inc.
State of Oklahoma County, Oklahoma, ss.


David Wiist Jr./Chesapeake Energy (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 18496, Oklahoma City, OK 73154-0496

SUBSCRIBED and SWORN TO before me this 17th day of JUNE
[Signature]
Notary Public

My Commission Expires: 2/26/12



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Jewell A 1-6 Plugging Daily Activity

02/25/2010

ROAD CLARKS TO LOCATION, HSM, RIG UP UNIT, TOHW RODS & TBG LAYING DOWN IN SINGLES, RIG UP LOG-TECH, RIH/W 4 1/2 CIBP & SET @ 2255', RIG DOWN & MOVE OUT LOG-TECH. DUMP 2 SX CMT ON CIBP, LOAD HOLE & PRESSURE TO 200 PSI (OK), DIG OUT CELLAR, CWISDFN.

02/26/2010

CREW TO LOCATION, HSM, RIG UP ALLIED, RIH/W TBG TO 740' & SPOT 15 SX GEL IN FRONT OF 50 SX CMT, PULL UP TO 280' & SPOT 50 SX CMT PLUG, PULL UP TO 60' & SPOT 20 SX CMT PLUG TO SURFACE. WAIT ON CMT TO CAP. SWFWE. NO KCC REP ON LOCATION. PLUGGING ORDERS GIVEN BY KCC REP. STEVE PHEIFER. RECOVERED, 110 - 3/4 RODS 2750'. 93 JTS 2 3/8 TBG 2775', 57 JTS 4 1/2 10.5 J55 CSG 1773'.

2/27 - 3/1

SDFWE

03/02/2010

CLARKS TO LOCATION, HSM, CEMENT FELL 10', WELD CAP ON, BACKFILL CELLAR & PIT, START CLEANING UP LOCATION. SDFN

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 2010

CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., LLC. 037104

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Medicine Lodge

DATE <u>2/26/10</u>	SEC <u>6</u>	TWP <u>30</u>	RANGE <u>11W</u>	CALLED OUT	ON LOCATION <u>8:30 A.M.</u>	JOB START <u>7:30 A.M.</u>	JOB FINISH <u>10:30 A.M.</u>
LEASE <u>Sanel</u>		WELL# <u>A1-6</u>		LOCATION <u>Esabel, Ks. 1/2, 3/4 S E into</u>		COUNTY <u>Ratt</u>	STATE <u>Ks.</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Clarke Corp
 TYPE OF JOB OHF
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH _____
 TUBING SIZE 2 3/8 DEPTH 740'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 200# MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT fresh

OWNER Chesapeake
 CEMENT
 AMOUNT ORDERED 15 sx gel
120 sx 60:40:40 gel
 COMMON Class A 72 @ _____
 POZMIX 48 @ _____
 GEL 19 @ _____
 CHLORIDE _____ @ _____
 ASC _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING _____ @ _____
 MILEAGE _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER MARK L.
 # 360-265 HELPER Scott P.
 BULK TRUCK
 # 364 DRIVER Carl B.
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:
Load hole w/ 150x gel
Spot plug @ 740' w/ 50sx
Spot plug @ 200' w/ 50sx
Circle to surface @ 60' w/ 200x

TOTAL _____

SERVICE

DEPTH OF JOB 740'
 PUMP TRUCK CHARGE _____
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 10 @ _____
 MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____

CHARGE TO: Chesapeake Oper.
 STREET _____
 CITY _____ STATE _____ ZIP _____

TOTAL _____

PLUG & FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
NONE @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME x C.K. Shahan
 SIGNATURE x [Signature]

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUN 09 2010
 CONSERVATION DIVISION
 WICHITA, KS



Regulatory Department

June 8, 2010

VIA UNITED PARCEL SERVICE

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 S. Market, Room 2078
Wichita, Kansas 67202

Re: Jewell A 1-6
6-30S-11W
Barber Co., Kansas

Dear Sir or Madam:

Enclosed are the original and one copy of the CP-4 for the referenced well.

Please direct all correspondence regarding this well, or any regulatory compliance matter, to my attention at the address below.

Thank you for your assistance in this matter.

Sincerely,

Chesapeake Operating, Inc.

A handwritten signature in black ink that reads "Sarah Rodriguez".

Sarah Rodriguez

Enclosures

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 09 2010

CONSERVATION DIVISION
WICHITA, KS