

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5088
Name: John J. Darrah, Jr.
Address 1: 225 N. Market #300
Address 2: _____
City: Wichita State: KS Zip: 67202 + _____
Contact Person: G. Stoepfelwerth
Phone: (620) 786-4046
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing/kc Depth to Top: 3420 Bottom: 3640 T.D. 3634
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 195-20966 - 0000
Spot Description: SE NW SW
_____ Sec. 11 Twp. 13 S. R. 21 East West
1,650 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: TREGO
Lease Name: Hamburg Well #: 4
Date Well Completed: MARCH 1982
The plugging proposal was approved on: MAY20, 2010 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 5/17/10
Plugging Completed: 5/21/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle-3861-71	Water/BP	SURFACE	8 5/8	241	NONE
Marmaton	Water/BP 3634	PRODUCTION	4 1/2	3900	NONE
Lansing/KC	3420-3640 oil&water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set packer on 2 3/8" tubing @1804, QRBP @ 2021 to squeeze casing leak. Pumped 150 sx neat cement w/ 2% CaCl. No Pressure, ordered 250 sx more cement, mixed and pumped. Ran in with bit on tubing, tagged bottom @ 1962 drilled and washed to & recovered QRBP; bottom 2235. Pumped 100 sx 60-40 poz 4%gel w/500#hulls, pumped 25 more sx wait, 45min, pumped 125 sx AA. Pumped 25 sx w/ 2%CaCl and displaced, wait 3 hrs. tagged cement @ 1620. Mixed and pumped cement to fill hole. Pulled tubing & topped out. Total today 150 Sx.

Plugging Contractor License #: 32382 Name: Swift Services
Address 1: P.O. Box 466 Address 2: _____
City: Ness City State: KS Zip: 67560 + 0466
Phone: (785) 798-2387

Name of Party Responsible for Plugging Fees: John J. Darrah, Jr.
State of Kansas County, Sedgwick, ss.
G.P. Stoepfelwerth, II, AGENT Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] 6/28/10

RECEIVED
JUN 09 2010
KCC WICHITA