

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5399  
Name: AmericanEnergies Corporation  
Address 1: 155 North Market  
Address 2: Suite 710  
City: Wichita State: KS Zip: 67202 + \_\_\_\_\_  
Contact Person: Mindy Wooten  
Phone: (316) 201-1134  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 135-23658-0000  
Spot Description: NE NW NW  
NE NW NW Sec. 36 Twp. 18/6 R. 22  East  West  
330 Feet from  North  South Line of Section  
990 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ness  
Lease Name: Ummel Ranch Well #: 2  
Date Well Completed: 04/13/92  
The plugging proposal was approved on: 02/24/10 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 05/17/10  
Plugging Completed: 05/17/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
	Water/Sands	Surface	8 5/8"	255	None
	Water/Sands	Production	5 1/2"	4390	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5/17/10 - Rigged up Swift Cement. Mixed 50 sx of 60/40 poz with 4% gel and went down casing. Followed with 42 bbls water with gel, then 200 sx cement and loaded hole. Hooked up to surface and pumped 25 sx to 500#. Swift Ticket #17911

RECEIVED  
JUN 04 2010  
KCC WICHITA

Plugging Contractor License #: 5399 Name: American Energies Corporation  
Address 1: 155 North Market Address 2: Suite 710  
City: Wichita State: KS Zip: 67202 + \_\_\_\_\_  
Phone: (316) 263-5785  
Name of Party Responsible for Plugging Fees: Alan L. DeGood, President  
State of Kansas County, Sedgwick, ss.  
Alan L. DeGood, President  Employee of Operator or  Operator on above-described well,  
(Print Name)  
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Alan L. DeGood



P. O. Box 466  
Ness City, KS 67560  
Off: 785-798-2300



# Invoice

DATE	INVOICE #
5/17/2010	17911

BILL TO
American Energies Corporation 155 North Market Street 710 Market Centre Building Wichita, KS 67202

- Acidizing
- Cement
- Tool Rental

5071

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#2	Ummel Ranch	Ness		Oil	Workover	PTA	Brett
PRICE REF.	DESCRIPTION				QTY	UM	UNIT PRICE	AMOUNT
575W	Mileage - 1 Way				30	Miles	5.00	150.00T
576W-P	Pump Charge - PTA				1	Job	750.00	750.00T
581W	Service Charge Cement				300	Sacks	1.50	450.00T
583W	Drayage				378.15	Ton Miles	1.00	378.15T
328-4	60/40 Pozmix (4% Gel)				300		9.75	2,925.00T
275	Cotton Seed Hulls				3	Sack(s)	25.00	75.00T
279	Bentonite Gel				6	Sack(s)	25.00	150.00T
290	D-Air				3	Gallon(s)	35.00	105.00T
	Subtotal							4,983.15
	Sales Tax Ness County						5.30%	264.11

ENTD MAY 24 2010

RECEIVED  
JUN 04 2010  
KCC WICHITA

<b>We Appreciate Your Business!</b>	<b>Total</b>	\$5,247.26
-------------------------------------	--------------	------------

REC'D MAY 19 2010



CHARGE TO: American Energies  
 ADDRESS \_\_\_\_\_  
 CITY, STATE, ZIP CODE \_\_\_\_\_

TICKET  
17911

PAGE 1 OF 1

SERVICE LOCATIONS  
 1. Ness City KS WELL/PROJECT NO. 2 LEASE Ummell Ranch COUNTY/PARISH Ness STATE KS CITY Ness City DATE 5-17-10 OWNER \_\_\_\_\_  
 2. \_\_\_\_\_ TICKET TYPE  SERVICE CONTRACTOR \_\_\_\_\_ RIG NAME/NO. \_\_\_\_\_ SHIPPED VIA Brownell DELIVERED TO \_\_\_\_\_ ORDER NO. \_\_\_\_\_  
 3. \_\_\_\_\_  SALES \_\_\_\_\_  
 4. \_\_\_\_\_ WELL TYPE Oil WELL CATEGORY Abandon JOB PURPOSE Plug to Abandon WELL PERMIT NO. \_\_\_\_\_ WELL LOCATION Brownell KE, YLS, Ginto  
 REFERRAL LOCATION \_\_\_\_\_ INVOICE INSTRUCTIONS \_\_\_\_\_

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE Trk #114	30	mi			5.00	150.00
576P		1			Pump Charge PTA		hr			750.00	750.00
581		1			Service Charge Cement	300	skts			1.50	450.00
583		1			Drayage	378.15	TM			1.00	378.15
328-4		1			60/90 Pozmix 4% Gel	300	skts			9.75	2925.00
275		1			Cotton Seed Hulls	3	skts			25.00	75.00
279		1			Bentonite Gel	6	skts			25.00	150.00
290		1			D-Air	3	gal			35.00	105.00
RECEIVED											
JUN 04 2010											
KCC WICHITA											

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X [Signature]  
 DATE SIGNED 5-17-10 TIME SIGNED 1000  A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	AMOUNT
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4983	15
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				Ness TAX	264.11
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	5247.26
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

**CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES** The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR Brett Corsair APPROVAL \_\_\_\_\_

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 5-17-10 PAGE NO. 1

CUSTOMER: American Energies WELL NO. 2 LEASE Ummell Ranch JOB TYPE Plug to Abandon TICKET NO. 17911

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1000							On Location TD 4399 5K Perfs-4265-68
	1030	6			✓			Start Cement 50sks w/200#Hulls
		6	13		✓			Switch to Gel Spacer
		4 1/2	42		✓			Cement 200sks 60/40 4% Gel
		4 1/2	60		✓		150	Cement
			107.					Shut Down - Vacuum
			6.5				500	Cement Annulus 25sks - Held pres.
	1115		6.5					Top off 5 1/2 25sks
								Wash Truck
	1200							Job Complete
								Thank you Brett, Dave & John

RECEIVED  
JUN 04 2010  
KCC WICHITA

REC'D MAY 19 2010