

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: TDI, Inc.

Address: 1310 Bison Road, Hays, KS 67601

Phone: (785) 628-2593 Operator License #: 4787

Type of Well: D & A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 5-11-10 (Date)

by: Ed Schumacher (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15-051-25,964-0000

Lease Name: Richard

Well Number: 1

Spot Location (QQQQ): - NW - NE - NW

330 Feet from North / South Section Line

1,650 Feet from East / West Section Line

Sec. 10 Twp. 15 S. R. 18 East West

County: Ellis

Date Well Completed: 5-11-10

Plugging Commenced: 5-11-10

Plugging Completed: 5-11-10

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 8 5/8" casing, Put In 218', Pulled Out Cmt'd. w/150 sax.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 3,643', pump 25 sax cement thru drill pipe; run drill pipe to 1,220', pump 25 sax cement thru drill pipe; run drill pipe to 520', pump 100 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184 RECEIVED KANSAS CORPORATION COMMISSION

Address: PO Box 709, Russell, KS 67665 JUN 03 2010

Name of Party Responsible for Plugging Fees: TDI, Inc. State of KANSAS County, RUSSELL, ss. CONSERVATION DIVISION WICHITA, KS

Burton Beery Contractor (Employee of Operator or Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery

(Address) PO BOX 709, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 20th day of June, 2010

Ruth Phillips Notary Public

My Commission Expires:

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas RUTH PHILLIPS State of Kansas My Appt. Exp. 5-24-2011




Shields

Russell, Kansas

WELL LOG

Operator: TDI, Inc.
 Well: Richard #1
 Commenced: 5-5-2010
 Completed: 5-11-2010
 Contractor: Shields Drilling Co.

Well Description: 330' FNL, 1,650' FWL
 NW/4 Sec. 10-15S-18W
 Ellis Co., KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	218'	Cmtd. w/150 sax

Elevation: 2,028 K.B.

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	735'	
Sand	1,015'	
Sand & redbed	1,200'	
Anhydrite	1,240'	
Redbed & shale	1,905'	
Shale	2,655'	
Shale & lime	3,305'	
Lime	3,663'	
Arbuckle	3,730'	RTD

RECEIVED
 KANSAS CORPORATION COMMISSION

JUN 03 2010

CONSERVATION DIVISION
 WICHITA, KS

Notes