

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34318
Name: Berexco, L.L.C.
Address 1: P. O. Box 723
Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67637 + _____
Contact Person: Curtis Gabel
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
KCB Depth to Top: 3384' Bottom: 3388' T.D. _____
ARB Depth to Top: 3631' Bottom: 3656' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-03496-0000
Spot Description: _____
SW NW SE _____ Sec. 1 Twp. 12 S. R. 18 East West
1,530 Feet from North South Line of Section
2,880 ~~2,370~~ Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Karlin Well #: A-4
Date Well Completed: 8-27-51
The plugging proposal was approved on: _____ (Date)
by: Bruce Basye (KCC District Agent's Name)
Plugging Commenced: 5-26-10
Plugging Completed: 5-27-10 12:00 P.M.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
RECEIVED					
JUN 02 2010					
KCC WICHITA					
			8 5/8	128'	0
			4 1/2	3681'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing open end to 3600', rig up Allied. Mix 150 sks 60/40 Pos w/4% gel and 300# of hulls. Pull tubing to 1800', mix 75 sks cement w 300# hulls. Circulate to surface. Pull rest of tubing. Hook up to 8 5/8. Mix 25 sks, pump down 8 5/8 press to 300#, pump 10 sks down 4 1/2 and top off. Done plugging at 12:00 p.m. KCC rep Marvin Mills was present for plugging. Rig down and move off.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.
Address 1: P. O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67637 + _____
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.
State of Kansas County, Sedgwick, ss.
Curtis Gabel Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202