

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003
 Name: McCoy Petroleum Corporation
 Address 1: 8080 E. Central, Suite #300
 Address 2: _____
 City: Wichita State: KS Zip: 67206-2366
 Contact Person: Brent Reinhardt
 Phone: 316-636-2737

Type of Well (Check One): Oil Well Gas Well O&G D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2925' Bottom: 2934' T.D. 5960'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15-119-20818-00-00
 Spot Description: _____
 - C-SW-NE Sec 14 Twp 34 S. Rng. 28 East West
3300 Feet from North / South Line of Section
1980 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Meade
 Lease Name: DAVIS #1-14
 Date Well Completed: 11/24/90
 The plugging proposal was approved on: 11/1/09 (Date)
 by: Steve Durrant (KCC District Agent's Name)
 Plugging Commenced: 5/18/10
 Plugging Completed: 5/21/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	607'	0
		Production	5 1/2"	6008'	2250'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5/21/10: MIRU. Cut surface off 4' below ground. Sand at 2875'. Bailed 5 sacks cement. Ripped casing at 2410' and 2250'. Pulled casing up to 1220'. Pumped 15 sacks of gel, 50 sacks of cement and 100# of hulls. Pulled to 630'. Pumped 50 sacks with 100# hulls. Pulled to 40'. Pumped 35 sacks cement to surface.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
 Address 1: 190th US 56 Highway Address 2: _____
 City: Ellinwood, State: KS Zip: 67526
 Phone: 620-727-3410

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 01 2010

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
 State of Kansas County, Sedgwick, ss.

CONSERVATION DIVISION
WICHITA, KS

Scott Hampel Employee of Operator or Operator on above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel