

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003

Name: McCoy Petroleum Corporation

Address 1: 8080 E. Central, Suite #300

Address 2: _____

City: Wichita State: KS Zip: 67206-2366

Contact Person: Brent Reinhardt

Phone: 316-636-2737

Type of Well (Check One): Oil Well Gas Well O&G D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Miss	Depth to Top: <u>4766'</u>	Bottom: <u>4772'</u>	T.D. <u>4820'</u>
LKC "B"	Depth to Top: <u>4211'</u>	Bottom: <u>4213'</u>	T.D. <u>4820'</u>
	Depth to Top: _____	Bottom: _____	T.D. _____

API Number 15-047-21519 - 000D

Spot Description: _____

-SE-SW- SW Sec 4 Twp 26 S. Rng. 19 East West

330 Feet from North / South Line of Section
990 Feet from East / West Line of Section

Footages Calculated from Nearest Outside Section Corner: *ku*
 NE NW SE SW

County: Edwards "B"

Lease Name: FOX "B" GAS UNIT #2-4

Date Well Completed: 1/25/06

The plugging proposal was approved on: 5/10/10 (Date)

by: Steve Durrant (KCC District Agent's Name)

Plugging Commenced: 5/11/10

Plugging Completed: 5/12/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	337'	0
		Production	4 1/2"	4822'	2640'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5/12/10: MIRU. Pumped 25 sx cement with 150# hulls down 4 1/2" casing; displaced to 3975'. Tagged cement at 3975'. Cut surface off 4' below ground. Ripped casing at 2810' and 2640'. Pulled casing up to 1300'. Pumped 15 sacks of gel, 50 sacks of cement and 100# of hulls. Pulled to 360'. Pumped 50 sacks with 100# hulls. Pulled to 40'. Pumped 20 sacks cement to surface.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.

Address 1: 190th US 56 Highway Address 2: _____

City: Ellinwood, State: KS Zip: 67526

Phone: 620-727-3410

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel Employee of Operator or Operator on above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts statements and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel

ku