

4-15-88 15-167-03868-0001

6 100327

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-4600

SE/4, SEC. 16, T 11 S, R 15 W/E

1650 feet from S section line

2310 feet from E section line

Lease Name Howe Well # 1 SWD

County Russell 122.46

Well Total Depth 3768 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Operator: Gear Petroleum Co Inc.

Name & Address 1075 KSB Building

Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Gear Pet Co. License Number

Address As above

Company to plug at: Hour: 2:00 PM Day: 15 Month: April Year: 19 88

Plugging proposal received from Max Parsons

(company name) Gear Pet. (phone) 316-265-3351

were: 8 5/8" set at 200', 5 1/2" set at 3470 w/2250' sks cement.

Order 100 sks Common Cement, 400 sks 60/40 Pozmix w/8% Gel and 5 sks Hulls.

Plugging Proposal Received by Don Butcher, Geologist
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:00PM Day: 15 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Clean out hole to 550'. Tubing to 550' and pump

100 sks Common Cement. Pump 150 sks 60/40 Pozmix 8% Gel, add 3 sks Hulls and pump 150

sks 60/40, and pull tubing w/fluid level 40'. Pump 15 sks 60/40 w/1 sks Hulls and cementing.

Casing full.

Cemented by Allied CONSERVATION DIVISION
Wichita, Kansas

Remarks: No pressure because there was no bradenhead on the well, just open casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-29-88

21116

Signed David K. Wann (TECHNICIAN)
PIRT II

RECEIVED
6-20-88
JUN 20 1988