

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-147 21,840-0000

SE, Sec. 19, T 11 S, R 15 W/4

1260 feet from NS section line

1700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6656

Lease Name VONFELDT Well # 1

Operator: AMERICAN LARIAT INC  
Name & Address: BOX 926  
HAYS, KANS. 67601

County RUSSELL

Well Total Depth 3686 feet \$119.80

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 1003

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor SUN OIL WELL CEMENTING license Number

Address BOX 27 HAYS, KANS 67601

Company to plug at: Hour: 9:00 AM Day: 20th Month: APRIL Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO DON SMITH

(company name) AMERICAN LARIAT INC (phone) 628-8190

ware: 8 5/8" 1003 FT SR. CUL 1/500 ST ENT, 5 1/2" SET @ 3680 FT 1/325 OUT

Plug BACK T.O. 2210 FT PERFS. 2186'-2189 FT

NO PIPE RECOVERY, CEMENT ON BACK SIDE @ BOTTOM 2000 FT

ORDER 275 ST 50/50 FORMIX 4% GEL-3% CA-CL, 10 ST GEL, 4 ST HULLS

AND 5 1/2" PLUG PUMP IN WITH PUMP TRUCK, IN ANNULUS,

AND 8 5/8" 50. Signed [Signature] (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:50 AM Day: 20th Month: APRIL Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 275 ST 50/50 FORMIX 4% GEL-3% CA-CL, 10 ST GEL, 4 ST HULLS

AND 5 1/2" PLUG, PUMPED IN WITH PUMP TRUCK.

PUMPED IN 10 ST CNT, 3 ST HULLS, 40 ST CNT, 6 ST GEL.

RELEASED PLUG AND 125 ST CNT, MAX PRESSURE 1000 PSI SHUT IN @ 350 PSI

PUMPED 100 ST CNT 1/2 ST HULLS IN ANNULUS, MAX PRESSURE 400 PSI SHUT IN @ 350 PSI

Remarks: CEMENTED BY SUN CNT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

Signed [Signature] (TECHNICIAN) DOIC

FORM CP-2/3 Rev. 9-82

INVOICED APR 25 1983

DATE 5-3-83 CONSERVATION DIVISION Wichita, Kansas

INV. NO. 4133-W