

6 070768

5-16

167-21 833 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
SW \_\_\_\_\_, SEC. 19, T 11 S, R 15 W&X

1360 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9125

Lease Name Powell Well # 1

Operator: B. A. Younger Oil Co.  
Name & Address: Box 451  
Hays, Kansas 67601

County Russell 118.72

Well Total Depth 3653 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 989

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_  
Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: PM Day: 16 Month: May Year: 19 89

Plugging proposal received from B.A. Younger

(company name) B.A. Younger Oil Company (phone) \_\_\_\_\_

were: 8 5/8" 989' S.P. cwc w/550 sks; 5 1/2" casing set at 3653' w/150 sks cement.

Perfs at 3425' - 3458'. Bottom sanded to 3020' and w/5 sks cement. Recovered 1700'

of 5 1/2" casing/ Proposal 200 sks 60/40 Poz 8% Gel and 5 sk Hulls. Pump in 8 5/8" S.P. with

pump truck. Load S.P. with cement and shut in under pressure. Production Inc.

Pulled 5 1/2" casing.

RECEIVED  
STATE CORPORATION COMMISSION  
6-6-89  
JUN 6 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN) *MJS*

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15PM Day: 16 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Poz 8% Gel and 5 sks of cotton seed Hulls.

Pumped in 8 5/8" s.p. with pump truck. Pumped in 8 5/8" s.p. 25 sks cement followed w/175

sks cement w/5 sks Hulls mixed in, max pressure 800 psig. Shut in at 300 psig. Cemented

by Allied Cement., Russell, Total cement 200 sks.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (Do not check this box to reserve this plugging.)

DATE 6-8-89 *J.S.*

INV. NO. 25030

Signed *Marion J. Schmidt* (TECHNICIAN)