

15-167-01718-0000

6 060282

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APT NUMBER 15-
SE, SEC. 16, T. 11 S, R. 15 W18

990 feet from ~~11~~ S section line
2310 feet from ~~11~~ S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5109

Lease Name None Well # 1

Operator: Aylward Drilling Co.
Name & Address: 909 First Natl. Bank Bldg.
Wichita, Ks.
67202

County Russell

Well Total Depth 3400' 110.50 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 95' w/65 sh.

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated

Plugging Contractor Aylward Drilling Co. License Number 5109

Address 909 First Natl. Bank Bldg.

Company to plug at: Hour: 9:00 AM Day: 20 Month: July Year: 19 84

Plugging proposal received from Arnold Michael's

(company name) Aylward Drilling Co. (phone) _____

were: Order 150 sh. 50 per mix. 6% Gel. - 3% Cal. U. & 4 sh. hulls.

RECEIVED.

STATE CORPORATION COMMISSION

7-30-84

JUL 30 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Edith E. Shelton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 20 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" set at 95' w/65 sh. 5 1/2" at 3394' w/50 sh.

Top perf. at 3031'. Plug set at 960" could not get out. hole in casing at 580'. Squared w/400 sh. from 610' to surface.
Pumped in 8 5/8" - 500 pounds pressure. No cement.
Pumped in 5 1/2" 50 sh. cement w/1000 pounds pressure.

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

INVOICED

(did ~~not~~) observe this plugging.

DATE 7-31-84

Signed Edith E. Shelton (TECHNICIAN)

INV. NO. 2780