

12-27

6 041122

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-01,729-0000

E/2 SW SWSEC. 16, T 11 S, R 15 W/E

660 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6854

Lease Name Whitson Well # 2

Operator: B. P. Exp Inc.

County Russell 108.88

Name & Address Box 37

Well Total Depth 3350 feet

Gorham, Ks. 67640

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 953 w/560 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00 Day: 27 Month: Dec Year: 19 89

Plugging proposal received from Joel Stull

(company name) B. P. Exp (phone)

were: 5 1/2" casing set at 3338' w/175 sks. Perf at 2899' - 3210'

Perf casing at 975'.

Ordered 300 sks 65/35 poz 8% gel 2% cc and 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 PM Day: 27 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Set cement retainer at 2850': Run tubing to sting into

retainer and sq 100 sks at 500 psi to plug bottom, spotted gel to 1000';

Pulled tubing to 1000' and circ 75 sks cement to surface; pulled tubing; pulled

tubing and sq add 125 sks to circ cement up annulus from perfs at 975'; shut in annu-

lus and pressured up to 350# psi.

Remarks: (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION JAN 17 1990

Observe this plugging.

INVOICED JAN 24 1990

Signed Dennis L. Hamel (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

DATE

INV. NO. 27092