

12-515-167-36586-0000
3/1933 *260R*
API NUMBER 15-

U 6 041263
To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW NW, SEC. 16, T 11 S, R 15 W&E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245
Operator: Okmar Oil Co.
Name & Address: Box 723
Hays, Ks. 67601

Lease Name Hines Well # A 1
County Russell 110.50
Well Total Depth 3400 feet
Conductor Pipe: Size 20 feet 20 cement NA
Surface Casing: Size 10 feet 2192 cmt NA

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor B. J. titan License Number
Address Hays, Ks.

Company to plug at: Hour: 1:00 PM Day: 5 Month: Dec. Year: 19 90

Plugging proposal received from Ted Crawford

(company name) Okmar Oil Co. (phone)

were: 7" csing set at 3212 w/NA sks cement: perfs at 3378. O.H. to 3400; Perf
anhy at 1020; perf base dakota at 525; Hole in casing at 856; Ordered
500 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 800 sks hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:00 PM Day: 5th Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT R. I. H. w/tubing to 3100 Spt 200 sks cement w/800 lbs. hulls.

Pull up tubing to 1500: circ cement to surf w/150 sks. Hook up to 7"
casing sq add 200 sks. Max 400 lbs psi. S.I. 200 lbs. cement. Circ 7"
10 " annulus annulus. r.I.H. w/tubing in 20" casing to 100' circ cmt to surf.

1-7-91
JAN 7 1991

Remarks: 15 casing at 506; 12" at 1013; 8 1/2 at 2692; all of previous casing pulled out.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 17 1991

INV. NO. 30514

Gib.S

Signed *Dennis L. Hamel*
(TECHNICIAN)
Dennis L. Hamel