

9-10

4-010292

15-167-06135-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

N2 NW SW /4 SEC. 16, 11 S, 15 W
2310 feet from S section line
4620 feet from E section line

Operator license# 5363

Lease: Whitson Well # 1

Operator: Berexco, Inc.

County: Russell 109.43

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3367 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ None feet

Aband. oil well Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 10 Month: September Year: 1997

Plugging proposal received from: Curt Gabel

Company: Berexco, Inc. Phone: 913-628-6101

Were: Same as below.
Holes in casing at 520' and 1716' - 2553'.
Squeeze at 559' with 250 sxs cement.
BP at 2947'.
5 1/2" liner at 2910' - 3367'.
9-15-97

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None []

Completed: Hour: 2:00 P.M., Day: 10, Month: September, Year: 1997

Actual plugging report: Perfs at 1425' and 1010'. Ran tubing to 2910' and pumped 30 sxs gel, followed by 60 sxs 60/40 pozmix - 10% gel cement with 100# hulls. Pulled tubing to 1400' and pumped 80 sxs cement with 400# hulls. Pulled to 700' and pumped 85 sxs with 500# hulls. Circulated. Topped off with 10 sxs.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did [] / did not [] observe the plugging.
Con Man
(agent)

INVOICED

DATE 9-16-97

INV. NO. 49008
9-10