

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-04772-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 20-11S-15W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: KORTAN Well Number: 4  
County: RUSSELL Total Vertical Depth: 3456 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 131 w/125 sxs cmt  
Production: Size 5.5 feet: 3381 w/125 sxs cmt  
Liner: Size feet:

Well Type: SWD UIC Docket No: D03249.0 Date/Time to Plug: 10/25/2002 12:00 PM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (316) 772-8160

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/25/2002 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran in tubing with notched collar and cutrite.  
Hit bridge at 500'. Went through several bridges down to 950'.  
Got very hard drilling and tubing binding up.  
Pulled one joint. Circulated cement inside 5 1/2" with 160 sxs 60/40 pozmix - 10% gel cement.  
Pulled tubing. Tied onto 5 1/2" and circulated cement up backside with 50 sxs cement.  
Shut in backside and pumped 115 sxs cement with 400# hulls.  
Max. P.S.I. 700#. S.I.P. 400#.

RECEIVED  
10-31-02  
OCT 31 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

CASE MORRIS

(TECHNICIAN)

INVOICED

DATE 10-31-02

INV. NO. 2003060735

Form CP-2/3

OCT 30 2002

FERRELL DRILLING CO

#1

KORTON

20-11-15W  
SE NE SW

33

Contr. FERRELL DRILLING CO

RUSSELL

County

E 1831 RB

Comm.

Comp.

10-10-52

IP


SWDW

Tops	Depth	Datum
Awh	908	+923
LANS	2967	-1136
CONG	3281	-1450
ARB	3296	-1465
TD	3456	-1625

Casing

5" 3381 CO & DD

FAIRPORT POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS