

4-14

4-010249

15-167-06154-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- -

SW SE NE /4 SEC. 20, 11 S, 15 W  
2970 feet from S section line  
990 feet from E section line

Operator license# 5363

Lease: Durham RB Well # 2

Operator: Berexco, Inc.

County: Russell 102.38

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3150 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 920 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67601

4-29-97

Company to plug at: Hour: 4:00 P.M. Day: 14 Month: April Year: 1997

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: 913-628-6101

Were: Run 1" to 1000' and circulate. Run 1" down backside and circulate. 7" squeezed at 341' with 200 sxs in 1957. Ran line to 84' in 7" - 10 3/4" annulus. Tubing at 341'. Rods at 2375'. 7" packer at 2973'. Seating nipple at 3098'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ x ], None[ ]

Completed: Hour: 6:30 P.M., Day: 14, Month: April, Year: 1997

Actual plugging report: Ran 1" to 1023'. Circulated cement to surface with 165 sxs 60/40 pozmix - 10% gel. Had communication with backside at 10 3/4". Hooked onto 7" and pumped 215 sxs cement - circulated on backside 10 3/4".

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: GL

INVOICED

I did[ x ] / did not[ ] observe the plugging.

Car Morris (agent)

DATE APR 29 1997

NO. 48038