

350 R

4 050053

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-167-06576-0000

W/2 NE NE, SEC. 20, T 11 S, R 15 W/EX

4620 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Durham Well # b-1

Operator Okmar Oil Co.

County Russell 109.20

Name & Address Box 723

Well Total Depth 3360 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 10 feet 964

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Services License Number

Address

Company to plug at: Hour: 9:00AM Day: 31 Month: July Year: 19 90

Plugging proposal received from Ted Crawford

(company name) (phone)

were: Order 600 sks 65/35 poz 10% gel 1000 lbs. hulls. Well record:

10" at 964, 8 5/8 at 2693, 7" at 3109, 5 1/2 liner 3075 - 3291 and 4" from

3280 - 3360. Sq with 100 sks at 3021-25.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour 4:30PM Day: 31 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Drilled to 932. Pumped 285 sks 65/35 poz

10% down tubing cement circulated to surface from 7" and 8 5/8. Tubing stuck backed off 9 joints left 20 joints tubing in hole (approx 640).

Sq down 7" casing with 315/sks cement 200 lbs. hulls with max psi at 400 lbs.

Shut in psi at 100 lbs.

RECEIVED STATE CORPORATION COMMISSION

AUG - 7 1990

8-7-90

Remarks: If additional description is necessary, use BACK of this form.

INVOICED

(did / observe this plugging.

DATE AUG 15 1990

INV. NO. 28928

J. S.

Signed Marvin S. Miller (TECHNICIAN) Marvin Miller